BRUHAT BANGALORE MAHANAGARA PALIKE

FORM OF EXTRA ITEM RATE LIST-3, IN FORM NO. P.W.G.71.

: Developments works to be under taken in Ward No.05 of BBMP around Solid Waste Disposal Processing units Bellahalli, Bagaluru and Kattigenahalli Byatarayanapura

ost : 12.50 Crores

ame: A G Narayanaswamy

er No & Date:02/21-22, Dated:26.05.2021

	Description of work	Unit	Asper qty	Rate in Rupees	Amount(Rs)	Whether the items are alternative to the item in the tender, whether these are additional items or sometimes in Accepted tender	Whether the extra items are included in the sanctioned estimate	How the extra cost of the item is proposed to be met	Whether the item is indicated in the SR	Remarks
1	2	3	4	5	6	7	8	9	10	11
E-1	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 (Page, 25 Item 5.26.2)	Sqm	29.60	989.23	29281.21	Additional item	Yes	Met out from the overall savings		
E-4	KSRRB 300-Compaction KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. MORTH / Chapter 3	Sqm	10877.85	6.42	69835.81	Additional item	Yes	Met out from the overall savings		
E-6	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/trap/basalt material, mixing by mix in place method by rotavator at OMC,spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications. Clause 401 of MORTH V Revision. (Page, 153 Item 20.6)	Cum	571.48	1873.55	1070700.10	Additional item	Yes	Met out from the overall savings		
	Total				1169817.12					

Percentage of EIRL over the Tender Sancitoned = (EIRL amount / Cost of Sanctioned Tender) x 100 = 1.11%

20/06/22

Asst. Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore - 92

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Executive Engineer

Scanned by TapScanner